



3P Safety LLC

Crane Inspection • Safety Training • Staffing

309 N William St, Goldsboro, NC 27530
(252) 229-5238 • patrick.salazar@3psafety.net
3psafety.net

FORMAL QUOTE

Tower Crane Inspections — Columbia, South Carolina

QUOTE #	3PSI-2026-0928-DCG
DATE	September 28, 2026
VALID THROUGH	October 28, 2026 (30 days)
SERVICE LOCATION	Columbia, SC — jobsite address confirmed at scheduling
CONTACT	John Vallos • jvallos@donleyinc.com
SCOPE	One (1) tower crane — initial / post-erection + quarterly inspections
SCHEDULE	Initial at erection; quarterly (every 90 days) thereafter
PREPARED BY	Patrick Salazar, Lead Inspector

PREPARED FOR

Donley's Concrete Group

Attn: John Vallos
jvallos@donleyinc.com

Project: Tower crane — Columbia, SC
Billed per visit against the Donley's job / PO #

SCOPE OF WORK

3P Safety LLC will provide third-party tower crane inspection services for **Donley's Concrete Group** on the **Columbia, South Carolina** project. Each site visit covers a complete inspection of one (1) tower crane — an **initial / post-erection inspection** when the crane is erected on site, then **quarterly (90-day) inspections** for as long as the crane is in service — performed to **OSHA 29 CFR 1926 Subpart CC** (§1926.1412 and §1926.1435) and **ASME B30.3** by an **NCCCO-Certified Crane Inspector**. The crane receives a **written inspection report**, a **pass / fail (fit-for-service) determination**, and a dated inspection decal at each visit.

UNIT INSPECTED Tower Crane — make / model / serial to be confirmed • **INSPECTIONS** Initial / post-erection + quarterly (90-day) • **LOCATION** Columbia, SC •
REQUESTED BY John Vallos, Donley's

Structure & Connections

- Tower / mast sections & splices
- Slewing ring, turntable & kingpin
- Jib, counter-jib & apex / cat head
- Ties, bracing & base anchorage
- Bolts, pins, welds & structural members

Mechanical & Reeving

- Hoist, trolley & slewing drives
- Brakes, gearboxes & drums
- Wire rope, end terminations & sheaves
- Hook block & safety latch
- Counterweights & ballast

Electrical, Controls & Safety Devices

- Load moment indicator (LMI) & overload cut-outs
- Hoist / trolley / slew limit switches
- Anemometer & wind-speed alarm
- Operator cab controls & interlocks
- Warning devices & lighting

PRICING

Description	Amount
Initial / Post-Erection Tower Crane Inspection One (1) tower crane, Columbia, SC. Complete inspection after the crane is erected on site and before it is placed in service, to OSHA 29 CFR 1926 Subpart CC (§1926.1435) and ASME B30.3. Written report, pass / fail determination, and dated decal. Includes all travel.	\$1,650.00
Quarterly (90-Day) Tower Crane Inspection The same crane, every 90 days for as long as it is in service on the project (§1926.1412) — same scope, report, and decal as the initial inspection. Includes all travel.	\$1,500.00 / visit
Crane Operator Evaluation — OSHA 1926.1427(f) OPTIONAL ADD-ON Performed during a scheduled inspection visit. Documented practical evaluation of each operator on the project crane, with a signed evaluation record for Donley's file.	\$495.00 / operator

All-Inclusive Pricing (includes all travel)

\$1,650.00 initial • \$1,500.00 / quarterly visit

Flat, all-inclusive prices per site visit — include all travel to and from the site (mobilization, mileage, lodging, related costs); no additional trip charges. Additional tower cranes on the same site during the same visit can be added — quoted once the crane list is confirmed. Applicable state / local taxes, if any, are not included.

TERMS

- **Firm fixed prices, all-inclusive**, as listed above — no separate mileage, mobilization, lodging, or per-diem charges.
- Quote valid for **30 days** (through **October 28, 2026**); on acceptance, quarterly pricing holds for inspections scheduled through **September 30, 2027**.
- Inspections performed by an **NCCCO-Certified Crane Inspector** to OSHA 29 CFR 1926 Subpart CC (1926.1412 / 1926.1435) and ASME B30.3.
- Dates scheduled by mutual agreement — the initial inspection is coordinated with the erection schedule; quarterly inspections follow every 90 days. Client to provide safe access, current load charts, erection / maintenance records, and the operator / power needed for functional checks.
- Written inspection report with a pass / fail (fit-for-service) determination and dated decal at each visit; digital report delivered within **48 hours**.
- Scope **excludes load testing and non-destructive / dielectric testing** unless separately quoted. Deficiencies found are documented and reported — not repaired.
- Invoice issued on completion of each site visit, **Net 30**. Please reference the **Donley's project / PO number** on the acceptance.

PERFORMED & PREPARED BY

Patrick Salazar

Owner / Lead Inspector — NCCCO-Certified Crane Inspector
3P Safety LLC • September 28, 2026

ACCEPTED BY — DONLEY'S CONCRETE GROUP

Signature

Name & Title / Date • Project / PO #