



3P Safety LLC

Crane Inspection • Safety Training • Staffing

309 N William St, Goldsboro, NC 27530
(252) 229-5238 • patrick.salazar@3psafety.net
3psafety.net

FORMAL QUOTE

Tower Crane Inspection — Columbia, South Carolina

QUOTE #	3PSI-2026-0928-DCG
DATE	September 28, 2026
VALID THROUGH	October 28, 2026 (30 days)
SERVICE LOCATION	Columbia, SC — jobsite address confirmed at scheduling
CONTACT	John Vallos • jvallos@donleyinc.com
SCOPE	One (1) tower crane — third-party inspection
SCHEDULED	By mutual agreement — coordinated with Donley's
PREPARED BY	Patrick Salazar, Lead Inspector

PREPARED FOR

Donley's

Attn: John Vallos
jvallos@donleyinc.com

Project: Tower Crane Inspection
Columbia, South Carolina

SCOPE OF WORK

3P Safety LLC will perform a complete **third-party inspection of one (1) tower crane** at Donley's jobsite in **Columbia, South Carolina** — a **post-erection** inspection on a newly erected crane, or a **periodic (quarterly / annual)** inspection on a crane already in service, whichever the crane requires. Its load-bearing structure, tower and jib connections, power-transmission and reeving components, electrical systems, and safety devices are examined and functionally verified to **OSHA 29 CFR 1926 Subpart CC** (including §1926.1412 and §1926.1435) and the **ASME B30.3** tower-crane standard by an **NCCCO-Certified Crane Inspector**. The crane receives a **written inspection report**, a **pass / fail (fit-for-service) determination**, and a dated inspection decal on completion.

UNIT INSPECTED Tower Crane — make / model / serial to be confirmed • **INSPECTION TYPE** Post-erection or periodic (quarterly / annual) • **LOCATION** Columbia, SC • **REQUESTED BY** John Vallos, Donley's

Structure & Connections

- Tower / mast sections & splices
- Slewing ring, turntable & kingpin
- Jib, counter-jib & apex / cat head
- Ties, bracing & base anchorage
- Bolts, pins & pin retainers
- Welds & primary structural members

Mechanical & Reeving

- Hoist, trolley & slewing drives
- Brakes, gearboxes & drums
- Wire rope & end terminations
- Sheaves & reeving
- Hook block & safety latch
- Counterweights & ballast

Electrical, Controls & Safety Devices

- Load moment indicator (LMI)
- Anti-two-block & overload cut-outs
- Hoist / trolley / slew limit switches
- Anemometer & wind-speed alarm
- Operator cab controls & interlocks
- Warning devices & lighting

PRICING

Description	Amount
Tower Crane Inspection — One (1) Tower Crane, Columbia, SC Complete on-site third-party inspection of one (1) tower crane (post-erection or periodic) — structure, mechanical, electrical, and safety-device systems — to OSHA 29 CFR 1926 Subpart CC and ASME B30.3 by an NCCCO-Certified Crane Inspector. Includes written report, pass / fail determination, and dated decal. All travel to Columbia, South Carolina included.	\$1,500.00
Total — All-Inclusive (includes all travel)	\$1,500.00

Flat, all-inclusive price — includes all travel to and from the site (mobilization, mileage, related costs); no additional trip charges. Additional tower cranes on the same site can be inspected during the same visit — quoted on request. Applicable state / local taxes, if any, are not included.

TERMS

- **Firm fixed price of \$1,500.00, all-inclusive.** Includes all travel to and from the site — no separate mileage, mobilization, or trip charges.
- Quote valid for **30 days** from the issue date (through **October 28, 2026**).
- Inspection performed by an **NCCCO-Certified Crane Inspector** to OSHA 29 CFR 1926 Subpart CC and ASME B30.3.
- Inspection date scheduled by mutual agreement (for a post-erection inspection, on completion of erection and before the crane is placed in service); client to provide safe access to the crane, current load charts, erection / maintenance records, and any operator / power support needed for functional checks.
- Written inspection report with a pass / fail (fit-for-service) determination and dated decal provided on completion; digital report delivered within **48 hours**.
- Scope **excludes load testing and non-destructive / dielectric testing** unless separately quoted. Deficiencies found are documented and reported — not repaired.
- Invoiced on completion of the inspection, billed against the **Donley's job / PO number** (to be provided by Donley's). Payment **Net 30** from invoice date.

PERFORMED & PREPARED BY

Patrick Salazar

Owner / Lead Inspector — NCCCO-Certified Crane Inspector
3P Safety LLC • September 28, 2026

ACCEPTED BY

Signature

Name & Title / Date • PO # (if required)