



3P Safety LLC

Crane Inspection • Safety Training • Staffing

309 N William St, Goldsboro, NC 27530
(252) 229-5238 • patrick.salazar@3psafety.net
3psafety.net

FORMAL QUOTE

Tower Crane Inspections — USC Sumter Hall, Columbia, SC

QUOTE #	3PSI-2026-0928-DCG
DATE	September 28, 2026
VALID THROUGH	October 28, 2026 (30 days)
PROJECT	USC Sumter Hall — 1311 Blossom St., Columbia, SC 29201
CONTACT	John Vallos, Project Manager • jvallos@donleyinc.com
SCOPE	Two (2) tower cranes — initial + quarterly inspections
SCHEDULE	Crane 1 initial week of Oct. 5, 2026 • Crane 2 at erection • quarterly every 90 days
PREPARED BY	Patrick Salazar, Lead Inspector

PREPARED FOR

Donley's Concrete Group

Attn: John Vallos, Project Manager
jvallos@donleyinc.com

Project: USC Sumter Hall — Columbia, SC
Billed per visit against the Donley's job / PO #

SCOPE OF WORK

3P Safety LLC will provide third-party tower crane inspection services for **Donley's Concrete Group** on the **USC Sumter Hall** project in Columbia, SC — **two (2) tower cranes**. Each crane receives an **initial / post-erection inspection** with an **evaluation of its operator** when it is erected on site, then **quarterly (90-day) inspections** for as long as it is in service — performed to **OSHA 29 CFR 1926 Subpart CC** (§1926.1412 and §1926.1435) and **ASME B30.3** by an **NCCCO-Certified Crane Inspector**, with a **written inspection report**, a **pass / fail (fit-for-service) determination**, and a dated inspection decal for each crane at each visit.

UNITS INSPECTED Tower Crane 1 (ready week of Oct. 5) & Tower Crane 2 (a few months out) — make / model / serial to be confirmed • **LOCATION** 1311 Blossom St., Columbia, SC • **REQUESTED BY** John Vallos, Donley's

Structure & Connections

- Tower / mast sections & splices
- Slewing ring, turntable & kingpin
- Jib, counter-jib & apex / cat head
- Ties, bracing & base anchorage
- Bolts, pins, welds & structural members

Mechanical & Reeving

- Hoist, trolley & slewing drives
- Brakes, gearboxes & drums
- Wire rope, end terminations & sheaves
- Hook block & safety latch
- Counterweights & ballast

Electrical, Controls & Safety Devices

- Load moment indicator (LMI) & overload cut-outs
- Hoist / trolley / slew limit switches
- Anemometer & wind-speed alarm
- Operator cab controls & interlocks
- Warning devices & lighting

PRICING

Description	Amount
Initial / Post-Erection Tower Crane Inspection + Operator Evaluation	\$1,950.00 / crane
Each tower crane, after it is erected and before it is placed in service — Crane 1 the week of October 5, 2026; Crane 2 when it goes up. Complete inspection to OSHA 29 CFR 1926 Subpart CC (§1926.1435) and ASME B30.3, plus a documented practical evaluation of the crane operator (OSHA 1926.1427(f)). Written report, pass / fail determination, dated decal, and signed evaluation record. Includes all travel.	
Quarterly (90-Day) Tower Crane Inspection	\$1,500.00 / crane
Per crane, per visit: each crane every 90 days for as long as it is in service on the project (§1926.1412) — same scope, report, and decal as the initial inspection. Includes all travel.	

All-Inclusive Pricing (includes all travel)

\$1,950.00 initial • \$1,500.00 quarterly (per crane)

Flat, all-inclusive prices per crane, per site visit — include all travel to and from the site (mobilization, mileage, lodging, related costs); no additional trip charges. Evaluations for additional operators can be added — quoted on request. Applicable state / local taxes, if any, are not included.

TERMS

- **Firm fixed prices, all-inclusive**, as listed above — no separate mileage, mobilization, lodging, or per-diem charges.
- Quote valid for **30 days** (through **October 28, 2026**); on acceptance, these prices hold for both cranes' inspections scheduled through **September 30, 2027**.
- Inspections performed by an **NCCCO-Certified Crane Inspector** to OSHA 29 CFR 1926 Subpart CC (1926.1412 / 1926.1435) and ASME B30.3.
- Dates scheduled by mutual agreement — Crane 1's initial inspection the week of **October 5, 2026**, once erection is complete; Crane 2's when it is erected; quarterly inspections every 90 days after each crane's initial. Client to provide safe access, current load charts, erection / maintenance records, and the operator / power needed for functional checks.
- Written inspection report with a pass / fail (fit-for-service) determination and dated decal for each crane at each visit; digital report delivered within **48 hours**.
- Scope **excludes load testing and non-destructive / dielectric testing** unless separately quoted. Deficiencies found are documented and reported — not repaired.
- Invoice issued on completion of each site visit, **Net 30**. Please reference the **Donley's project / PO number** on the acceptance.

PREPARED BY

Patrick Salazar

Owner / Lead Inspector — NCCCO-Certified Crane Inspector
3P Safety LLC • September 28, 2026

ACCEPTED BY — DONLEY'S CONCRETE GROUP

Signature

Name & Title / Date • Project / PO #